

**SURVEY &
REMONUMENTATION**

DEC 01 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 278

For Corners in
GLADWIN
(County)

Located In: Corner Code#:

- | | | |
|---------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T. <u>18N</u> R. <u>02W</u> | <u>K-6</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

19 NOV 1999 2:03:22 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon
Set 1/4 Section Post
Wit-(1)W. Birch N50W 25
(2)Cedar 5 N85E 6

1956 W.S. Moore survey
Wit-none

1939 MSHD Axle Shaft
Wit-(3)N37W 72.60 Tel. Pole
(4)N63E 57.10 Fe Cor Post
(5)S69E 54.53 Fe Cor Post

1974 Lapham LCRC#90 & survey
Found 1 1/2" Bar in Mon Box
Wit-(6)N50W 91.55 Cor Fe Post
(7)S45W 69.43 T.P.
(8)S50E 95.74 P.P.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1 1/2" Iron in Monument Box 5 feet West of centerline M-18, opposite centerline road to West, and 5 feet North of 2-track road to East. Iron agrees with 1938 MSHD notes and measurements to K-7 and K-5. It also agrees with Moore (1956) and Lapham (1974) measurement to K-5

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 10/30/98

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6: 1/4 Corner common to Sections 13 & 14. Set 5/8" x 18" rod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:
S50°E Power Pole, nail & tag, 93.17' (MDOT)
N55°E Top Center R/W Mon 80.89' (MDOT)
N40°W 14" W. Pine, nail & tag, 96.80'
S75°W "X" in West Edge of North Wing Wall Culvert 64.90'
East 1/2" x 18" Iron Center 2-track 85.68'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-16-99