

SURVEY &
REMONUMENTATION

DEC 01 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 280

SECTION

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 18N R. 02W K-8
T. _____ R. _____
T. _____ R. _____
2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION
19 NOV 1999 2:03:50 PM
BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Geo H. Cannon 1978-88 Lapham 3 surveys
Old 1/4 Section Corner--Set Post Wit-same as (3), (4) & (5)
Wit-(1)Beech 7 N70W 22
(2)Do 6 S84E 29
1975 Lapham LCRC#117 1997 Lapham 2 surveys
Set P.K. Nail
Wit-(3)N85E 51.64 Fe Cor (7)S60E 56.07 12" Pine
(4)S80E 56.03 8" J. Pine (8)N75E 45.40 16" Pine
(5)West 41.16 Power Pole (9)S40W 45.50 16" Pine

1998 MDOT Fd P.K. Nail
See MDOT Plans#26011 for Loc & Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found P.K. Nail 4 feet +/- West of centerline M-18, 7 feet South of Fence to East, and opposite Fence to West. Nail agrees with witnesses (6), (7) & (8). Also agrees with measurements to K-9 and K-7 by MSHD 1938; Lapham 1970 and 1997; and MDOT 1998.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. Mark R. Robison
Date 10/30/98

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8: 1/4 Corner common to Sections 23 & 24. Set 5/8" x 18" rerod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

- Witnesses:
S60°E 12" Pine, nail & tag, 56.07'
S40°W 16" Pine, nail & tag, 45.50'
N75°E 16" Pine, nail & tag, 45.40'
West Power Pole, nail & tag, 39.55'
S40°W 12" Maple, nail & tag, 85.35'
N85°E Face Cable Sign 61.65'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-16-99