

SURVEY &  
REMONUMENTATION

DEC 01 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Gladwin County Remonumentation

LIBER 001 PAGE 282

SECTION

For Corners in  
GLADWIN

(County)

Located In:

Corner Code#:

- |                                       |                             |             |
|---------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey                 | T. <u>18N</u> R. <u>02W</u> | <u>K-10</u> |
|                                       | T. _____ R. _____           | _____       |
|                                       | T. _____ R. _____           | _____       |
| 2. Public Controlling in Section      | S. _____ T. _____ R. _____  | _____       |
|                                       | S. _____ T. _____ R. _____  | _____       |
| 3. Miscellaneous Property in Section  | S. _____ T. _____ R. _____  | _____       |
|                                       | S. _____ T. _____ R. _____  | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                             |             |
| 5. Private Claims _____               |                             |             |

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

19 NOV 1999 2:04:16 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon  
Set Post Old 1/4 Cor  
Wit-(1)Y. Birch 10 N80E 25  
(2)Hemlock 8 N63W 24

1980-86 Lapham 4 surveys  
Found P.K. Nail & Tag  
Wit-same as (3), (4) & (5)

1979 Lapham LCRC#252 & survey  
Set P.K. Nail MPOL  
Wit-(3)East Cor Post 57.90  
(4)N70W P.P. 73.15  
(5)S45E Fe. Post 73.35

1998 MDOT Found P.K. Hole  
Set P.K. Nail utilizing witness and  
survey data by Lapham  
See MDOT Plans#26011 for Loc & Wits

(Note-above not correct--Correct set at  
prorated gov't distance)

1998 Lapham  
Meas. Distance K-11 - K-10 = 2633.69  
Meas. Distance K-10 - K-9 = 2645.04

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found P.K. Nail set by MDOT in Northbound lane 5 feet+/- East of centerline.  
Nail agrees with witnesses (3) & (5). Also agrees with Lapham 1979, 1980 &  
1998 measurements to K-9 and K-11.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

See dossier for detailed report.

Co. Rep. [Signature]  
Date 10/30/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: 1/4 Corner common to Sections 25 & 26. Set 5/8" x 18" rered in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:

- East Corner Post, nail & tag, 57.90'
- S45°E Fence Post, nail & tag, 73.25'
- West 1/2" Rerod 70.50'
- N70°W Gate Post, nail & tag, 67.70' (MDOT)
- S45°W 1/2" Rerod 84.10' (witness only)
- N55°W 1/2" Rerod 83.35' (witness only)



Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 11-16-99