

SURVEY & REMONUMENTATION

DEC 01 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 283

SECTION

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 02W K-11
 T. _____ R. _____
 T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-REMONUMENTATION

19 NOV 1999 2:04:30 PM

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon
 Set Cor Sec Post Secs 25,26,35&36
 Wit-(1)Cedar 9 N50E 16
 (2)Do 9 S63W 7

1971 Lapham LCRC#3-71
 Fd Mon Box
 Wit-none

1939 MSHD-road plans & notes
 Axle Shaft
 Wit-(3)N42W 63.75 Tel Pole
 (4)S70W 84.04 20" Poplar
 (5)S54W 65.82 NE Cor Gas Pump Isle

1974 Lapham LCRC#99
 Fd 2" Bar in Mon Box
 Wit-(9)N45W 82.82 P.P.
 (10)N65E 90.76 P.P.
 (11)S55E 68.05 C/L Top Conc R/W
 Mon

1978 Lapham-survey
 Fd 2" Iron Mon Box
 Wit-same as (9), (10) & (14)

1979 Lapham -survey
 Wit-same as (12), (13) & (14)

1960 Edmands Eng.
 Plow Point brought 1/2" Iron to surface
 Wit-(6)P.P. SW 55.0
 (7)P.P. NW 65.9
 (8)Fence Cor NE 40.8
 Hwy wits same as (3), (4) & (5)

1977 Lapham LCRC#151 & 2 surveys
 Fd Mon Box
 Wit-(12)N45W 73.80 R/W Marker
 (13) N45E 74.45 R/W Marker
 (14) S45E 68.10 R/W Marker

1996 Lapham Fd Mon Box
 Wit-same as (9),(10)&(14)

1971-96 Lapham working dwg

1998 MDOT Found 2" Bar in Mon Box
 See MDOT Plans#26011 for Loc & Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 2" Bar in Monument Box in centerline of M-18, 7 feet North of centerline road to East. Bar agrees with witnesses (9) & (10). Also agrees with Measurement by MSHD (1938), Lapham (1990), and MDOT (1998) to Corner K-12. Also agrees with MDOT Plans#26011 for location and witnesses.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 10/30/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: Corner common to Sections 25, 26, 35 & 36. Set 5/8" x 18" rered in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:
 S80°W P.P., nail & tag, 97.89' (MDOT)
 N50°W T. Pole, spike, 82.86' (MDOT)
 N45°W, 1/2" x 18" Rerod, 84.10'

S20°E East Leg Sign, nail & tag, 155.68' (MDOT)
 S45°E, 1/2" x 18" Rerod, 94.70'
 East, P.K. Nail, Centerline Asphalt 93.20'



Signed by Mark R. Robison Date 11-16-99
 Surveyor's Michigan License No. 27458