

SURVEY & REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

DEC 01 1999

Filing Requirement of Act 74, Mich. P.A. 1970

Gladwin County Remonumentation

LIBER 001 PAGE 285

For Corners in SECTION
GLADWIN

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>18N</u> R. <u>02W</u>	<u>K-13</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

19 NOV 1999 2:04:59 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon	1974 Lapham LCRC#99 Fd 2" Bar in Mon Box	
1938 MSHD road plans & field notes Axle with Gear Boat Spike on centerline	Wit-(6)N65W 70.75 P.P. (7)S50W 60.70 C/L Top Conc R/W Marker (8)N50E 106.82 15" Cottonwood	1983-86 Lapham 6 surveys & work dwgs Wit-same as (6), (7) & (8)
Wit-(3)N42W 61.40 to Tel Pole (4)S55W 56.05 to BM in 14" Poplar (5)S55E 55.70 to Tel Pole	1982 Fluharty LCRC#277 Fd 1 1/2" Iron in Mon Box Wit-(9)12" Willow S35E 148.00 (10)18" Poplar N50E 106.37 (11)NE Cor Conc R/W Marker S60W 60.70	1998 MDOT Found 1 1/2" Iron Rod in Mon Box See MDOT Plans#26011 for Loc & Wits
1960+/- Edmands Eng. work dwgs Wit-same as (3), (4) & (5)		

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1 1/2" Iron in Monument Box at intersection M-18 and county road East-West. Iron agrees with witnesses (8), (9) & (10) and MDOT 1998 witnesses. Also agrees with 1938 MSHD, 1970 Lapham and 1998 MDOT measurement to North (K-12).

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 10/30/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: Corner common to Sections 35 & 36, T18N, R2W, and Sections 1 & 2, T17N, R2W, on township line. Set 5/8" x 18" rerod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:
S30°E 24" Willow, nail & tag, 147.80' (MDOT)
S50°E 4" x 4" Post, nail & ribbon, 62.20' (MDOT)
N65°E 4" x 4" Post, nail & ribbon, 66.68' (MDOT)
N50°E 24" Cottonwood, nail & tag, 106.10' (MDOT)
N45°E 1/2" x 18" Rerod 92.37'
East, P.K. Nail, Centerline 80.57'
West, P.K. Nail, Centerline 81.34'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-16-99