

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

<u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>1E</u> <u>L13</u>	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on Feb. 14, 2011 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L13 - 1837 - GLO - L. Clason - Set 1/4 Post
 1) S. Maple 12" N51°W 26 L.
 2) S. Maple 5" N42°E 25 L.
 - 1930's - CCC Notes - West 40; Set Random 1/4 Post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L13 - Standard 1/4 corner common to Section 36, T19N, R1E - No GLO evidence found. Set 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe by single proportion on line of parallel between corners 'K13' and 'M13'. Corner in lowland hardwoods swamp. DNR Monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L13 - 4" DNR Aluminum Cap on 1" x 5' long galv. iron pipe
 Set Blue Carsonite Post 1' North
 N8°E 19.40' to set N & T in W. side 8" R. Maple
 N75°E 19.85' to set N & T in N. side 6" R. Maple scribed 'XBT'
 S7°W 30.43' to set N & T in E. side 10" R. Maple
 S23°W 1.89' to set N & T in E. side 7" R. Maple scribed "1/4 SCBT"
 S75°W 13.82' to set N & T in S. side 4" R. Maple scribed 'XBT'
 West 5.28' to 'L1', T18N, R1E - DNR Mon



Signed by: Craig W. McVean Date: 1/26/2012
 Surveyor's Michigan License No.: 39088