

FEB 18 1994

PAGE 06


DEC 29 '93 AM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>1E</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____



GLADWIN COUNTY
REGISTER OF DEEDS
BY *Donna House*

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1846 JOHN MULLETT, INT. PRINCIPAL MERIDIAN 53.43 CH N. OF COR. T19 & 20 N, RANGE 1 W, SET POST
 TAMARACK 7" N 24°E, 21 LKS P. 97
 TAM 8" S.E. 41 LKS
 03-07-61 GILBERT, 3/4" ROD IN MON. BOX (P.I.) M.S.H.D. WITNESS CARD
 N 42°30'E, 53.21' - N. SIDE, 4" TRIPLE MAPLE
 N 59°00'E, 93.97' - N. SIDE, CLUMP OF 4" MAPLES
 S 66°00'E, 67.53' - S. SIDE, 9" MAPLE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 5/8" x 36" BAR IN MON. BOX. EXCAVATED TO 3' DEPTH, DID NOT FIND ANY OTHER EVIDENCE.
 FOUND OLD FENCE POSTS ON FENCE TO EAST, ALSO NEWER BOARD FENCE AND CONC. MONUMENT.
 FOUND RECORDED WITNESSES:
 3/4" ROD IN MON. BOX (P.I.)
 N 42°30'E 53.21' - N. SIDE, 4" TRIPLE MAPLE
 N 59°00'E, 93.97' - N. SIDE, CLUMP OF 4" MAPLES
 S 66°00'E, 67.53' - S. SIDE 9" MAPLE

This Corner established in Gladwin County Remonumentation Program.
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" x 36" RE-ROD WITH 2" GLADWIN COUNTY MONUMENT CAP IN MONUMENT BOX.
 N 42°30'E, 52.90' - N. SIDE, REMAINS OF TRIPLE MAPLE
 N 59°E, 94.05' - N. SIDE, CLUMP OF 4 MAPLES
 S 66°E, 67.35' - N. SIDE, 15" MAPLE
 EAST, 32.95' - CONCRETE MONUMENT
 S 65°E, 38.4' - 10" WHITE PINE



Signed by Paul B. Lapham Date 12-08-93
 Surveyor's Michigan License No. 9433