

FEB 18 1994

DEC 29 93 AM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in


GLADWIN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 19N R 1E E-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____



GLADWIN COUNTY REGISTER OF DEEDS
W. J. Jones

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER NOT SET BY G.L.O., INTENDED TO BE SET MIDWAY BETWEEN N.W. & S.W. SECTION CORNERS.
 01-14-92 C.F. ROSER, LCRC #336

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND D.N.R. MONUMENT & CEDAR POST, SET BY C.F. ROSER FOR L.C.R.C. #336
 FOUND RECORDED WITNESSES:
 N 10°W, 7.6' - 4" W. PINE
 N 50°E, 70.72' - POWER POLE
 S 30°E, 8.9' - 5" W. BIRCH (CLP. 3)
 S 45°W, 5.2' - 3" W. PINE

ACCEPTED D.N.R. MONUMENT

This Corner established in Gladwin County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 ACCEPTED D.N.R. MONUMENT & CEDAR POST
 N 10°W, 7.6' - 4" W. PINE
 N 50°E, 70.72' - POWER POLE
 S 30°E, 8.9' - 5" W. BIRCH (CLP. 3)
 S 45°W, 5.2' - 3" W. PINE



Signed by Paul B. Lapham
 Surveyor's Michigan License No. 9433

Date 12-08-93