

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>1W</u>	<u>K6</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Joshua R. Davidson, in a field survey on November 4, 2013 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14	●	13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K6 – ¼ corner common to sections 13 & 14, T19N, R1W

- 1877 – GLO Resurvey by Merrill – set post for 1/4 sec cor – 1) Tamarack 16" S2°E lks. No other standing trees near.
- 1984 – Unrecorded Survey by C. Eugene Ostling, PS #12026 – West ¼ post – 5/8" Bar – 2) P. Pole NE 76.45'; 3) F. Post West 26.8'.
- 1984 – Section 13 computation sheet by C. Eugene Ostling, PS #12026 – No corner description given.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K6 – ¼ corner common to sections 13 & 14, T19N, R1W

Found 5/8" X 12" bar 6' West of centerline North-South gravel road. Measured 76.71' to found Mag Nail in power pole to Northeast, (#2), and 26± to remains of wood fence post to West, (#3). No GLO evidence was found. Distance South to K7 measures 2625.58'-grid (2640'- GLO). Accepted 5/8" X 12" bar as the best available evidence of the position of the original corner, and replaced it with a stamped 3" DNR brass cap on 5/8" x 34" long rebar with 4" x 6" long PVC pipe filled with concrete around cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K6 – stamped 3" DNR brass cap on 5/8" x 34" long rebar with 4" x 6" long PVC pipe filled with concrete around cap. – Buried 0.7' below road bed surface.

- N42°E 76.71' to found MAG nail in NE. side power pole (#2)
- S56°E 42.58' to set nail & tag in SW. side 16" Spruce
- S77°W 48.52' to set nail & tag above found nail in N. side 12" Spruce
- N30°W 62.90' to set nail & tag in E. side 14" R. Pine

Signed by: Joshua R. Davidson
Surveyor's Michigan License No.: 46659

Date: 12/16/2013

