

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 110

For corners in

GLADWIN
(County)

Located In:

Corner Code #

1. Public Land Survey

T	18N	R	1W	D - 11
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:25 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T GALE MERRILL
SET 1/4 SEC. POST
WIT.-(1)HEMLOCK 8 N17W 05
(2)MAPLE 6 S15E 28

1994 PAUL LAPHAM SURVEY
SET C.I. FROM SEC. SUBD.
WIT.-(5)N10W 42.85 20" W PINE N&T
(6)N75E 51.55 8" W PINE N&T
(7)S35W 67.88 24" W PINE N&T
(8)S05E 37.08 5" MAPLE N&T

1995 PAUL LAPHAM SURVEY
WIT.-SAME AS (5),(6),(7)&(8)

1900 DOANE SURVEY-ESTABLISH POST
SET CEDAR POST 4" X 4" X 4" & GAS PIPE
WIT.-(3)PINE STUMP 24 N63 1/4W 21 LKS
(4)DO 24 N7 1/2E 47

1994 PAUL LAPHAM SURVEY
FOUND 1/2" IRON
WIT.-SAME AS (5),(6),(7)&(8)

APPROVED LAND CORNER
P.A. 45 of 1990
Gladwin County

Co. Rep. Mark R. Robison
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND C.I. IN CENTER OF COUNTY ROAD OPPOSITE VERY OLD FENCE POST TO NORTH; POSSIBLE 1900 SURVEY-MATCHED WITNESSES (5),(6),(7)&(8). SET GLADWIN RE-MON IN PLACE OF FOUND C.I. & WITNESSES.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

D-11: 1/4 CORNER COMMON TO SECTIONS 29 & 32
SET 5/8" X 3/8" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:
N10W 42.85 20" W. PINE, N&T
N75E 51.55 8" W. PINE, N&T
S35W 67.88 24" W. PINE, N&T
S05E 37.08 5" MAPLE, N&T



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96