

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 112

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 19N R 1W	F - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:25 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. GALE MERRILL
WIT.-(1)CEDAR 12 FOR 1/4 SEC. POST

1908 KNOX SURVEY
WIT.-NONE

1979 PAUL LAPHAM-WORKING DRAWING

1992 PAUL LAPHAM-WORKING DRAWING

1993 PAUL LAPHAM-WORKING DRAWING

1994 PAUL LAPHAM SURVEY
SET 1/2" C.I. FROM 1979 P. LAPHAM SURVEY
WIT.-(2)N10W 20.50 8" ELM N&T
(3)N10E 14.55 16" POPLAR N&T
(4)S50W 72.65 16" POPLAR N&T
(5)S40E 39.75 6" POPLAR N&T

1998 PAUL LAPHAM SURVEY
WIT.-SAME AS (2),(3),(4)&(5)

APPROVED LAND CORNER
P.A. 74 of 1970
Gladwin County
Co. Rep. [Signature]
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND C.I.#9433, 12' NORTH OF C/L E-W CO. ROAD. FOUND WIT. (2),(3),(4)&(5) AS REC. & MEAS. FOUND C.I.#26459, SOUTH 33.15. SET GLADWIN RE-MON IN POSITION OF FOUND C.I.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11: 1/4 CORNER COMMON TO SECTIONS 28 & 33
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:
NORTH 6" BASS WOOD, N&T, 51.35'
SOUTH BOLT IN 4" X 5" METAL POST 43.45'
N60W 36" QUAD (4) MAPLES, N&T, 66.64'
S50W 18" POPLAR, N&T, 72.65'
S40E 6" POPLAR, N&T, 39.75'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96