

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

001 PAGE 114

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>1W</u>	<u>G - 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:26 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1877 T. GALE MERRILL
WIT.-(1)HEMLOCK FOR 1/4 SEC. POST | 1979 PAUL LAPHAM SURVEY
WIT.-SAME AS (2),(3),(4)&(5) |
| 1979 PAUL LAPHAM L.C.R.C. #235
FOUND 1/2" IRON
WIT.-(2)WEST COR. POST 34.75
(3)EAST COR. POST 33.35
(4)S40W POST 45.80
(5)S45W 5" BIRCH 52.85 | 1979 PAUL LAPHAM-WORKING DRAWING
1992 PAUL LAPHAM-WORKING DRAWING
SECTION SUBDIVISION |

APPROVED LAND CORNER
F. 1995 of 1990
Gladwin County

Co. Rep. [Signature]
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND P.K. NAIL OVER 1" X 12" BOLT SPIKE, 0.5' BELOW SURFACE OF ASPHALT ROAD IN C/L OF ROAD, 2'+/- NORTH OF FENCE TO EAST--OPPOSITE REMAINS OF COR. POST TO WEST. FOUND WITNESS (3); REC 33.35, MEAS. 33.35. SET GLADWIN RE-MON FROM FOUND BOLT SPIKE & WITNESS (3).

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12: 1/4 CORNER COMMON TO SECTIONS 33 & 34
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458 IN MONUMENT BOX

- WITNESSES:
- | | |
|----------------------------------|-----------------------------|
| N85W 12" MAPLE, N&T, 66.50' | N80E 6" W PINE, N&T, 39.56' |
| S45W CLUMP 6" BIRCH, N&T, 56.00' | NORTH, P.K. NAIL, 2.0' |
| S45E 6" W. PINE, N&T, 57.78' | EAST, P.K. NAIL, 2.0' |



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96