

GLADWIN COUNTY REMONUMENTATION

LIBER 001 PAGE 190

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>1W</u>	<u>I - 13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:22 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1877 T. Gale Merrill
Set Post
Wit.-(1)N55W 38 links 12" Hemlock
(2)N49E 17 links 8" Hemlock | 1992 Gray L.C.R.C.#340
Found 1/2" bar
Wit.-(6)AZ 325, 41.80' fence post
(7)AZ 52, 70.05' power pole
(8)AZ 94, 99.05' - 1/2" rod
(9)AZ 176, 35.45' - 10" poplar |
| 1990 Lapham survey
Found 1/2" rod
Wit.-(3)N45E Power Pole 70.00'
(4)S05E 10" Poplar 35.48'
(5)N45W Fence Post 41.80' | 1993 Lapham working drawing
1995 Lapham working drawing
Found 1/2" iron |

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod in county T-road to North, in centerline E-W, 4' West of centerline North. Found (4) & (9); recorded 35.48', measured 35.4' to center of tree. Found (3); recorded 70.00', measured 70.00 to face. Found (5) & (6) as recorded and measured--41.80'. Set Gladwin County Re-mon in place of found 1/2" x 18" rerod.

GLO recorded 99.0, measured 99.05.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: Corner on township line, common to Sections 34 & 35.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

- Witnesses:
N45E Power Pole, nail & tag, 70.05'
S05E 14" Poplar, nail & tag, 35.45'
S45W Triple 8" Elm, nail & tag, 106.50'
N45W Fence Post, nail & tag, 41.80'
East, NW Cor., Sec. 2, T18N, R1W, Gladwin County Re-mon-99.05'

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-7-97

