

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 191

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>1W</u>	<u>J - 13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED -Remonumentation

17 OCT 97 1:22 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on May 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. Gale Merrill Set Post
  - 1995 Lapham survey & working dwg. Set capped iron
  - Wit-(1)N11W 44 links 26" Pine
  - (2)N25E 55 links 12" Pine
  - Wit-(7)N10W 36.8' - 6" R. Pine
  - (8)N20E 39.4' - 24" W. Pine
  - (9)S45W 68.25' - 24" Maple
  - (10)S10E 61.90' - 16" W. Pine
  - 1992 Gray L.C.R.C.#340 Set iron
  - Wit-(3)AZ 27, 51.80' Power Pole
  - (4)AZ 348, 36.58' - 1" Red Pine
  - (5)AZ 227, 67.90' - 14" Maple
  - (6)AZ 192, 66.24 - 16" Maple

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 5/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron in centerline of county road 1' below surface. Found witnesses (7), (8), (9) & (10) as recorded and measured. Found witnesses (3), (4) & (5); no corner found. Witnesses place corner 0.85' West and 0.1 South of found capped iron. Set Gladwin County Re-mon in place of found capped iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13: Corner on township line, Section 35.  
Set 5/8" x 36" rered with Gladwin County Re-mon Cap marked P.S.#27458.  
Witnesses:  
N10W 5" R. Pine, N&T, 36.80'  
S12W 16" Maple, N&T, 66.45'  
N70E 18" W. Pine, N&T, 39.41'  
S10E 12" W. Pine, N&T, 61.90'  
East, N 1/4 Cor., Sec. 2, T18N, R1W, Gladwin County Re-mon, 167.00'  
S45W 16" Maple, N&T, 68.65'  
N27E P.P., N&T, 51.40'

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 10-7-97

