

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 192

For corners in

GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey

T 19N R 1W

K-13

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED -Remonumentation

17 OCT 97 1:22 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on April 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. Gale Merrill  
Set Post  
Wit.-(1)N2W 67 links 18" Pine  
(2)N59W 63 links 10" Beech

1995 Lapham survey & working dwg.  
Set corner capped iron at  
GLO offset distance 232.32'  
Wit.-(3)S20W 48.05' - 12" J. Pine  
(4)S40E 48.30' - 16" J. Pine  
(5)N05E 38.10' - 6" J. Pine  
(6)N25W 43.05' - 16" J. Pine

APPROVED LAND CORNER  
P.A. 315 of 1990  
Gladwin County

Co. Rep. J. H. Merrill  
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron 1 ft. below surface in centerline of county road 232.32' West of Northeast Corner of Section 2, T18N, R1W. Found (3), (4), (5) & (6) as recorded and measured. Set Gladwin County Re-mon in place of found iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: Corner on township line, common to Sections 35 & 36.  
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.  
Witnesses:  
S20W 12" J. Pine, nail & tag, 48.05'  
N05W 6" J. Pine, N&T, 38.10'  
S40E 16" J. Pine, nail & tag, 48.30'  
N25W 16" J. Pine, N&T, 43.05'  
South 8" J. Pine, nail & tag, 57.90'  
East, NE Cor. of Sec. 2, T18N, R1W, Gladwin County Re-mon 232.32'

SURVEY &  
REMONUMENTATION

JAN 08 1998

SECTION

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-7-97

