


FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 29 '93 AM

COMMISSION For corners in

Table with columns: GLADWIN (County), Located In: (Town/Range), Corner Code #. Row 1: Public Land Survey, T 19N R 1W, M-1.



Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1833 NICHOLSON, SET POST, CORNER T19 & 20N, R1W, P. 99; 1877 T. MERRILL, POST COR. TWP. 19 & 20N, R1W P.648; BIRCH 11" S 42°W, 40 LKS; ASPEN 16" N 40-1/2°W 15 LKS; 11-30-62 GILBERT, 1" PIPE IN MON. BOX, M.S.H.D. WITNESS CARD; 07-30-75 LAPHAM, LCRC #120

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 5/8" ROD IN MSHD MON. BOX. EXCAVATED TO 3' DEPTH - FOUND NO OTHER EVIDENCE. FOUND NO RECORDED WITNESSES.

This Corner established in Gladwin County Remonumentation Program. See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET 5/8" X 36" RE-ROD WITH 2" GLADWIN COUNTY MONUMENT CAP IN MONUMENT BOX. S 20°E, 95.00' - POWER POLE; S 35°W, 61.29' - 8" WHITE PINE; N 35°W, 63.70' - 12" POPLAR; N 75°E, 54.72' - 8" ASH



Signed by Paul B. Lapham Date 12-08-93
Surveyor's Michigan License No. 9433