

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Gladwin Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |   |            |   |           |           |
|--------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey                | T | <u>19N</u> | R | <u>2E</u> | <u>M8</u> |
|                                      | T | _____      | R | _____     | _____     |
| 2. Property Controlling in Section   | S | T          | R | _____     | _____     |
|                                      | S | T          | R | _____     | _____     |
| 3. Miscellaneous Property in Section | S | T          | R | _____     | _____     |
|                                      | S | T          | R | _____     | _____     |

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Feb. 2, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

M8 - GLO - Set 1/4 Post - L. Clason - 1837  
 W. Pine 20" S66°W 15 L.  
 W. Pine 15" N39°W 19 L.  
 - CCC Notes - 1930's - Random N 200 CH.  
 Set random post.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

M8 - Standard 1/4 Corner common to Sec. 19, T19N, R3E and Sec. 24, T19N, R2E - No conclusive GLO evidence. Set 4" DNR Alum. Cap on 1" x 36" Galv. iron pipe single proportion to GLO between 'M7' and 'M11' in-line with N-S fence. This position being about 8' West of straight line between 'M7' and 'M11'. DNR Mon. accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M8 - 4" DNR Alum. Cap on 1" X 36" Galv. iron pipe.  
 Set Blue Carsonite Post 1' W.  
 N56°E 56.01' to set N & T in NW side 14" R. Maple scribed 'XBT'  
 S63°E 65.40' to set N & T in N side 14" Oak scribed 'XBT'  
 S54°W 141.28' to set N & T in NW side 13" Oak scribed 'XBT'  
 N10°W 95.08' to set N & T in E side 3" Oak



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007