

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>19N</u> R <u>2E</u>	<u>J1</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on May 3, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1										●			
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

J1 – GLO – None  
 - CCC Notes – 1930's  
 West 120.00 – Set Random post

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

J1 – Closing North ¼ corner of Section 2, T19N, R2E - Found 2 – 1 ½" pipe lying on their side disturbed and not in place in this area. Apparently removed by timber operations. Could not recover old position. Thus set stamped 4" Aluminum DNR cap on 1" x 36" galvanized iron pipe midway and on standard line between fd. 'I-1' and re-established 'K1' per standard BLM procedure. DNR monument accepted as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J1 – 4" stamped DNR Aluminum cap on 1" x 36" galv. iron pipe  
 N22°W 35.07' to set N & T in SW side 5" Oak  
 N64°E 25.33' to set N & T in SE side 2" Oak  
 S30°W 49.01' to set N & T in NW side 6" Oak  
 West 7.52' to 'J13', T20N, R2E – DNR Mon.  
 Set Blue Carsonite Post 1' South



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007