

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Gladwin Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>19N</u>	R	<u>2E</u>	<u>I-1</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 26, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 – GLO – Intersect Townline 13 L. East of section corner for sections 34 & 35 of T20N, R2E.

Set post at intersection – J. Mullett – 1846
 Hemlock 6" S25°W 53 L.
 Hemlock 14" S35°E 37 L.

- CCC Notes –1930's- West on N. Bdy. of Sec. 2, T19N, R2E- 160:00 CH.- Set random mile post- Sec. post is 94 ½ N. & 3 E. of random post. N. random between Sec. 2 & 3 – 400 CH.-Set random mile post-1.50 E. of grade stake. Random post for Sec. 2 & 3 is 2.62 N & 31 E. of post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-1 – Closing corner common to sections 2 & 3, T19N, R2E - Fd. 1 ½" iron pipe broken off at ground. Fits GLO distance to Fd. 'I-13', T20N, R2E, which has evidence of original BT. 1 ½" iron pipe consistent with CCC monumentation found E & W. 1 ½" iron pipe on standard line and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 – Set Stamped 2 ½" Aluminum cap on 5/8" x 34" rebar inside fd. 1 ½" iron pipe.
 West 8.43' (8.58' – GLO) to 'I-13' of T20N, R2E – 2 ½" Alum. cap
 N52°W 50.58' to set ½" x 18' rebar
 S34°E 81.17' to set N & T in SW side 2" Oak
 N68°E 17.84' to set N & T in SE side 1" Oak
 Set Blue Carsonite Post 1' South.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007