

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Gladwin _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey		T <u>19N</u>	R <u>2E</u>		H1
		T _____	R _____		_____
2. Property Controlling in Section	S _____	T _____	R _____		_____
	S _____	T _____	R _____		_____
3. Miscellaneous Property in Section	S _____	T _____	R _____		_____
	S _____	T _____	R _____		_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Nov. 8, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H1 – GLO – None
 - CCC Notes – 1930's – West on
 N. Bdy of Sec. 3 – 200 CH – Set random post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H1 – Closing N ¼ Cor. of Sec. 3, T19N, R2E – Searched for evidence of CCC position West of found CCC position at 'H13', T20N, R2E but nothing found. Set 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe midway between 'G1' and 'I-1' on Standard line. Falls in swamp. 4" DNR Mon. accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H1 – 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe – Up 1.4'
 Set Blue Carsonite Post 1' S.
 East 9.75' to 'H13', T20N, R2E – 2 ½" Alum. Cap in Fd. 1 ½" iron pipe
 N48°E 60.28' to Fd. N & T in NW side 8" R. Maple scribed 'SCBT'
 S33°W 50.67' to Fd. N & T in SE side 12" R. Maple scribed 'XBT'
 N32°W 49.22' to set N & T in SW side 5" W. Pine

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5				4		3		2	1
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													