

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Gladwin (County)

- |                                      |   |            |   |           |           |
|--------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey                | T | <u>19N</u> | R | <u>2E</u> | <u>F1</u> |
|                                      | T | _____      | R | _____     | _____     |
| 2. Property Controlling in Section   | S | _____      | T | _____     | R         |
|                                      | S | _____      | T | _____     | R         |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | R         |
|                                      | S | _____      | T | _____     | R         |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 5, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F1 – GLO – Not set in original Survey  
- CCC Notes – 1930's – West on N. Bdy of Sec. 4. 280.00 CH – Set Random 1/4 Post. South on 1/4 Line Sec. 4.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F1 – Closing 1/4 Corner common to Sec. 4, T19N, R2E – From 'F13', T20N, R2E measured West 29.01' to Fd. 5/8" CIR #4672 – 0.99' South of Standard line – on East side of broken concrete mon. w/ 1/2" iron which is 29.24' W. of 'F13' and 1.03' S. of standard line. The concrete Mon. & 5/8" CIR line up with old firelane to South. The Record GLO closing at 'E1' is 40 Links West of 'E13'. The record GLO closing at 'G1' is 48 Links West of 'G13'. This averages to 44 Links = 29.04' for average closing at 'F1' – 'F13' positions. Thus accept the 5/8" CIR and Broke Conc. Mon. as the best available evidence of the position of the longitude of the corner and set 2 1/2" Brass Cap on 5/8" x 34" rebar 29.04' West of F13 – T20N, R2E on the Standard Line. 2 1/2" Brass Cap accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F1 – Stamped 2 1/2" Brass Cap on 5/8" x 34" rebar w/ 4" PVC w/ conc. around cap – Down 0.5. Add some crockery around. South 0.99' to 5/8" CIR #4672 on E. Side Broken Conc. Mon – Amended Monuments. East 29.04' to 'F13', T20N, R2E – 2 1/2" Brass Cap S16°E 63.23' to set N & T in W. side 23" R. Maple scribed 'CCBT' S40°W 29.82' to set N & T in NW side 4" R. Maple scribed 'CCBT' N55°W 43.42' to set N & T in NE side 10" Tamarack scribed 'CCBT' East 54' to set Blue Carsonite Post w/ Loc. Tag



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 5/9/2007