

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Gladwin (County)

1. Public Land Survey T 19N R 2E E2  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on March 27, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	●	4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E2 – GLO – Set ¼ Post – J. Mullett – 1846  
Hemlock 10" N46°E 19 L.  
Hemlock 8" S44°W 33 L.  
- CCC Notes – 1930's – North Between Sec. 4 & 5 – 440:00 – Set Random ¼ Post  
1:20 S. & 2.12 W. is old post  
- DNR Cor. Record – LCRC #16 – K. J. Ostling – 1971 – Fd. 4" x 4" square post as described in  
CCC survey between 1930 & 1940. Replaced w/ Dept. Mon.; 24" W. P. Stp. N85°W 14.4';  
7" S. Maple S25°E 72.3'; 14" Tri. S. Maple N67°E 61.7'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E2 – ¼ Corner common to Sec. 4 & 5 - Fd. 4" DOC (DNR) Alum. Cap on 1" galv. iron pipe per Ostling. No GLO evidence. Fits stps. of both Maple Wits. and WPS per Ostling. DOC Mon. accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E2 – 4" DOC (DNR) Alum. Cap on 1" galv. iron pipe  
Set Blue Carsonite Post 1' SE  
S67°W 11.46' to set N & T in N. side 4" R. Maple scribed 'XBT'  
S42°W 49.47' to set N & T in NW side 5" R. Pine  
N9°W 58.08' to set N & T in W. side 3" R. Pine  
N85°E 89.62' to set N & T in N. side 5" R. Maple  
S28°E 17.25' to fd. Hack mark on 28" WPS.



Signed by: Craig W. McVean Date: 5/9/2007  
Surveyor's Michigan License No.: 39088