

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Gladwin _____ Located In _____ Corner Code # _____
 (County)

- | | | | | | |
|--------------------------------------|-----------|-------------|------------|---------|--|
| 1. Public Land Survey | T _____ | R _____ | | | |
| | T _____ | R _____ | | | |
| 2. Property Controlling in Section | S 8 _____ | T 19N _____ | R 2E _____ | 1 _____ | |
| | S _____ | T _____ | R _____ | | |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | | |
| | S _____ | T _____ | R _____ | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on April 11, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | ● | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1 - Rec. Sur. - L. 1, p. 392 & 395 - A. V. Courtright - 1974
 Set 5/8" steel rod; S75°W 12" Tw. Poplar 32.22';
 S20°E 7" Poplar 11.23'; N75°E 8" Poplar 21.02'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 - W. 1/16 Cor. Common to Sec. 5 & 8, T19N, R2E - Fd. broken Cap #4672 on 1/2" I.D. iron pipe per Rec. Survey. Centerline of E-W gravel rd. is 54' N. 1/2" CIP is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1 - Replaced broken cap w/ stamped 2" Alum. Cap on existing 1/2" iron pipe.
 North 21.05' to fd. 1/2" CIP # 4672
 N62°E 28.23' to set N & T in SE side 7" W. Pine
 N32°E 38.14' to set N & T in NW side P.P.
 S49°E 14.98' to set N & T in SW side 3" R. Maple
 Set Blue Carsonite Post w/ loc. Tag 1' SE



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007