

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>19</u> N. <u>0.</u> , R. <u>2</u> E. <u>0.</u>	<u>F-7; G-7; G-8;</u> <u>G-9</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT_____		
5. PRIVATE CLAIMS_____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 5, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a

Decree of a Court of law: _____

C. Continued:


<u>G-8</u>	<u>G-9</u>
Set DNR Monument	Set DNR monument
3" Jack Pine S12°W 69.6'	8" Jack Pine N63°W 35.7'
10" Jack Pine S10°E 92.7'	8" Jack Pine N47°E 48.6'
6" Cedar Post N85°W 6.0'	

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F-7 - Set corner by proportionate measurement midway and on line between section corners.
 - G-7 - Set corner at intersection of roads N-S, E-W.
No other conclusive evidence was found.
 - G-8 - Set corner by proportionate measurement midway and on line between section corners in N-S road.
 - G-9 - Set corner at intersection of roads N and E. Fits with call to stream east. No other conclusive evidence was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>F-7</u>	<u>G-7</u>
Set DNR monument & cedar post	Set DNR monument
10" Red Maple N29°W 23.2'	20" Red Maple N37°W 28.6'
6" Black Ash S30°E 10.0'	6" Red Maple S16°E 55.0'
½ of road South 22.0'	

SIGNED BY Carl F. Roser 03-13-85 DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)