

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 339

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 19N R. 2W A-1
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:27:37 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 Nicholson 3-11-77 Meyers Unrecorded survey Set R.R. spike Wit-N45E 87.13 P.P. S45W 80.77 P.P. S30W 41.47 Ced. Post
4-25-08 Johnson CSR 4-135 & 5-73 All Gov't Cors Fd Wit-Pine Stp. 28" N7W 79 Tel. Pole 8" N43 1/2E 51 1/2
1955 Moore--Gladwin Co. Plat of Miller Subd--Sec 6, T19N, R2W
8-14-79 Sedgman, R.R. Spike Wit-N40E 87.03 P.P. S35E 80.73 P.P. N65W 81.95 T.P.
3-15-80 Sedgman--Sketch of survey Sec 31, T20N, R2W Gladwin Co.
4-18-90 Wilcox LCRC#606 Set 1/2" rebar Wit-West 8.0 C.L. road to North N45E 87.10 P.P. S10W 72.92 4" Elm South 33.05 3/8" Rebar

Recorded in LCRC 250-97 Clare County Record

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Clare County Remon in Monument box. Agrees with recorded witnesses in LCRC#250-97 Clare Co., Michigan Public Records. Accepted as corner of record.

See dossier for detailed report on corner A-1.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-2-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Found 5/8" x 36" rered with Clare Co. Remon cap marked P.S. 27458 in Monument Box. Accepted as best available evidence to perpetuate position of corner A-1.

- Witnesses:
N67°E 131.60', nail & tag, 10" Elm
N17°E 111.02', South end 24" C.M.P.
N45°E 84.90', nail & tag, P.P.
N24°W 74.66', Center of Tele. Riser
S34°E 78.80', nail & tag, P.P.



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00