

SURVEY & REMONUMENTATION

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **85**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T19N R 2W	H-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:53 A.M.

RONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 LEVI H. CANNON
SET 1/4 POST
WIT.-(1)HEMLOCK 15" N72°E 9
(2)CEDAR 8" N36°W 20

1966 LAPHAM
WORKING DWG.
NO. WITNESSES

1966 CALDWELL
WITNESSES & WORKING DWG.
FOUND 3/4" PIPE
WIT.-(3)N3°E 67.0 P.P.
(4)N3°E COR. FE POST 25.45'
(5)N50°E 40.65' 3RD FENCE POST
(6)S45°E 42.25' COR. FENCE POST
(7)NORTH 33.00 IRON

1993 LAPHAM L.C.R.C. #349
FOUND 3/4" IRON
WIT.-(8)N03°E POWER POLE 66.95'
(9)S03°W 12" ELM 41.38'
(10)S03°E 4" PINE 53.80'
(11)EAST 2" PIPE 31.35'

Co. Rep. Paul B. Lapham

Date 12/18/95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO CORNER FOUND, DESTROYED THRU ROAD CONSTRUCTION, SET GLADWIN RE-MON FROM WITNESSES (8), (9), (10) & (11) MATCHES WITNESSES (3), AND LAPHAM'S OFFSET DIST. REC. 31.25', MEAS. 31.35'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County



This Corner established in Gladwin County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13: SOUTH 1/4 CORNER SECTION 34
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP. MARKED P.S. #9433 IN MONUMENT BOX.

WITNESSES:
N03°E 66.95' - NAIL IN POWER POLE
N30°W 41.38' - NAIL & TAG IN 12" ELM
S20°E 39.05' - NAIL & TAG IN 6" SPRUCE
EAST 31.35' - GLADWIN RE-MON CLOSING CORNER H-1 T18N R2W
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95