

**SURVEY &
REMONUMENTATION**

JAN 17 1996

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER **001** PAGE **90**

For corners in

COMMISSION

GLADWIN
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 19N R 2W</u> | <u>1-7</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:54 A.M.

RONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY--NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 LEVI H. CANNON
SET POST
WIT.-(1)W. PINE 12" N53°E 4'
(2)BEECH 10" S27°W 33'

1987 LAPHAM SURVEY #G-877794
WIT.-SAME AS (3) (4) & (5) ABOVE

1988 LAPHAM SURVEY #G-888620
WIT.- SAME AS (3) (4) & (5) ABOVE

1910 GLADWIN COUNTY SURVEY RECORDS DWG. ONLY

1975 PAUL LAPHAM L.C.R.C. #108
FOUND 3/8" IRON
WIT.-(3)N45°E 44.97' FENCE POST
(4)S45°E 44.52' TELE. POLE
(5)N45°W 50.80' POWER POLE

1991 LAPHAM UNRECORDED L.C.R.C. FOR COUNTY ROAD CONSTRUCTION
FOUND 3/8" IRON
WIT.-(6)N45°W POWER POLE 50.52'
(7)N45°E CORNER POST 46.42'
(8)S45°E TELE. RISER 44.52'
(9)N70°W N. TOP CENTER 18" C.M.P. 57.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON INTERSECTION COUNTY ROADS, EXCAVATED FOUND NO OTHER CORNERS, SET GLADWIN MON. IN PLACE OF FOUND 3/8" IRON, MATCHED WITNESSES (4), (6), (7) & (8)

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7: CORNER COMMON TO SECTIONS 14, 15, 22 & 23
SET 5/8"x36" RE-ROD WITH GLADWIN RE-MON CAP MARKED NO. 9433

WITNESSES:
N45°W 50.50' - NAIL & TAG IN POWER POLE
N45°E 46.70' - NAIL & TAG IN CORNER POST
S45°E 44.65' - NAIL & TAG IN TELE. RISER & POLE
S45°W 50.87' - NAIL & TAG IN CORNER POST



APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. Paul B. Lapham
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95