

**SURVEY &
REMONUMENTATION**

JAN 17 1996

LIBER **001** PAGE **92**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:55 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T19N R 2W	1-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1856 LEVI H. CANNON SET 1/4 POST WIT.-(1)BEECH 16" S85°W 31' (2)BEECH 14" N86°E 23'	1950 DUNDAS & EDMANDS WORKING DWG. & WITNESSES WIT.-(4)N.W. 20" OAK 64.2' (5)S.W. TELE. POLE 46.6' (6)S.E. ANCHOR POST 75.8' FOUND 1/2" PIPE (7)33.1' GUY POST (8)27.25' E. POWER POLE (9)N.W. 44.4' POWER POLE (10)N.E. 42.4' POST (11)S.W. 64.3' 10" ELM	1973 LAPHAM L.C.R.C. #74 FOUND 1/4" BAR WIT.-(12)N45°W 49.82' TELE. POLE (13)N45°E 41.95' TELE. POLE (14)S80°W 107.13' 24" OAK TREE	1991 LAPHAM UNRECORDED L.C.R.C. FOR COUNTY ROAD CONSTRUCTION FOUND 3/8" IRON WIT.-(15)N40°W 16" MAPLE 85.25' (16)N45°E TELE. POLE RISER 41.87' (17)S80°W 24" OAK 107.00' (18)S20°E 8" W. PINE 157.35'
1900 GLADWIN COUNTY SURVEY DWG. NO WITNESSES		1973 LAPHAM SURVEY WITNESSES SAME AS L.C.R.C. #74	1992 LAPHAM SET C.I.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON IN INTERSECTION OF COUNTY ROAD. REPLACE WITH GLADWIN RE-MON, MATCHES WITNESSES.
(12) (14) (15) THRU (18).

APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/18/95

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-9: CORNER COMMON TO SECTIONS 22, 23, 26 & 27
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY REMON CAP MARKED NO. 9433 IN MONUMENT BOX

WITNESSES:
N40°W 85.25' - NAIL & TAG IN 16" MAPLE
S45°E 41.87' - NAIL & TAG IN TELE. POLE RISER
S80°W 107.00' - NAIL & TAG IN 24" OAK
S20°E 157.35' - NAIL & TAG IN 8" W. PINE
NORTH P.K. NAIL 2.0'
EAST P.E. NAIL 2.0'



Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95