

**SURVEY &
MONUMENTATION**

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **86**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>2W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:53 A.M.

HOWIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|---|---|
| 1856 LEVI H. CANNON
WIT.-(1)W. PINE 22" 1/4 CORNER
(2)W. PINE 18" S42°W 24' | 1984 PAUL LAPHAM SURVEY
WIT.-(5), (6) & (7) ABOVE | 1991 PAUL LAPHAM
UNRECORDED WIT. FOR GLADWIN CO.
ROAD CONST.
FOUND 1/2" IRON |
| 1972 PAUL LAPHAM SURVEY
WIT.-(3)N30°E 63.4' 18" ELM
(4)S45°E 61.2' POWER POLE | 1984 JOHN MEYERS L.C.R.C. #285
K-11 & K-10 REVERSED
WIT.-(5), (6) & (7) ABOVE | WIT.-(10)S50°E POWER POLE 49.20'
(11)S60°W FENCE POST 65.62'
(12)S75°E 24" SPRUCE 109.25'
(13)N80°E 6" ASH 104.00' |
| 1983 PAUL LAPHAM SURVEY
FOUND 1/2" IRON
WIT.-(5)N45°E FENCE COR. 48.25'
(6)S40°E POWER POLE 61.73'
(7)S45°W FENCE POST 55.80' | 1988 PAUL LAPHAM SURVEY
WIT.-(5) (6) & (7) ABOVE | |
| | 1985 PAUL LAPHAM SURVEY
FOUND IRON
WIT.-(8)N30°E 18" ELM 63.40'
(9)S45°E POWER POLE 61.20' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN PATCH 8" BELOW SURFACE IN INTERSECTION ASPHALT CROSSROADS
RESET CORNER LOCATION FROM WITNESSES (10) & (11), AND FOUND COR.
FITS RECONSTRUCTED LOCATION OF WITNESS (5) POST WAS LEANING WAS SET UPRIGHT



This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: CORNER COMMON TO SECTIONS 25 & 26
SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY REMON CAP IN MON. BOX. MARKED P.S. #9433

WITNESSES:
S50°E 49.20' - NAIL & TAG IN POWER POLE
S60°W 65.62' - NAIL & TAG IN FENCE POST
N80°E 104.98' - NAIL & TAG IN 6" ASH
S75°E 109.25' - NAIL & TAG IN 24" SPRUCE
S45°W 103.72' - N.E. CORNER METAL BLDG.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. J. H. Meyers
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95