

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 87

For corners in

| GLADWIN (County) | Located In: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 19N R 2W | K-11 |
| | T R | |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:53 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 LEVI H. CANNON
WIT.-(1)POST BEECH 13 S46°W 15
(2)HEMLOCK 8 N41°E 26
 - 1960 PAUL LAPHAM SURVEY
NO WITNESSES
 - 1972 PAUL LAPHAM SURVEY
1" BOLT RAISE WITH 1/2" IRON
WIT.-(3)S50°W 40 COTTONWOOD 36.54'
(4)N20°W 36" MAPLE 83.05'
(5)EAST 4" STEEL COR. POST 33.33'
 - 1983 JOHN MEYERS L.C.R.C.
FOUND 1/2" IRON
WIT.-SAME AS (3), (4) & (5)
 - 1983-1989 PAUL B. LAPHAM SURVEYS
WIT.-SAME AS (3), (4) & (5)
 - 1993 JOHN MEYERS L.C.R.C. #349
FOUND 1/2" IRON
WIT.-(6)EAST CENTER STEEL POST 33.33'
(7)WEST POWER POLE 34.13'
(8)EAST POWER POLE 34.40'
(9)N80°W 10" APPLE 45.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND P.K. NAIL, EXCAVATED FOUND 1/2" IRON ROD 12" BELOW SURFACE ASPHALT SURFACE, EXCAVATED 36"
FOUND IRON, DID NOT REMOVE, SET GLADWIN MONUMENT FROM FOUND IRONS AND WITNESSES (7), (8) & (9)

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: CORNER COMMON TO 25, 26, 35 & 36
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

WITNESSES:
EAST CENTER 33.30' - STEEL POST
WEST 34.06' - NAIL & TAG IN POWER POLE
EAST 34.44' - NAIL & TAG IN POWER POLE
N80°W 45.95' - NAIL & TAG IN 10" APPLE
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'



APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95