

JAN 17 1996

COMMISSION AND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

For corners in

26 DEC 95 10:54 A.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 19N R 2W	K-13
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1838 HENRY NICHOLSON SET POST  
WIT.-(1)HEMLOCK 13 N65°E 05  
(2)HEMLOCK 14 N84°W 16
  - 1950 MOORE SET 3/4" PIPE  
WIT.-(3)POWER POLE N80°W 2.35'  
(4)POWER POLE S10°E 7.50'  
(5)POWER POLE N10°W 23.20'
  - 1969 LAPHAM SURVEY FOUND 1" IRON  
NO WITNESSES
  - 1969 LAPHAM L.C.R.C. #69 FOUND 3/4" PIPE  
WITNESSES SAME AS (3), (4) & (5)
  - 1973 LAPHAM SURVEY #3163 SAME AS L.C.R.C. #69
  - 1975 LAPHAM SURVEY #750618 SAME AS L.C.R.C. #69
  - 1976 LAPHAM SURVEY #750802 SAME AS L.C.R.C. #69

- 1976 CONSUMERS POWER CO. SURVEY & WITNESS FOUND 1/2" PIPE  
WIT.-(6)POLE WEST 2.31'  
(7)POLE S18°W 7.07'  
(8)POLE N2°W 23.18'
- 1991 LAPHAM SURVEY #G-911084 WITNESSES SAME AS (6), (7) & (8)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE, 12 SOUTH OF TRAIL, EXCAVATED, NO OTHER COR'S FOUND, MATCH WITNESSES (8), ALL OTHER POLES MOVED, SET GLADWIN RE-MON IN PLACE OF FOUND 1/2" PIPE

This Corner established in Gladwin County Remonumentation Program.  
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: 35-36 SEC. CORNER ON TOWNSHIP LINE  
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

- WITNESSES:
- N10°W 23.13' - NAIL & TAG IN POWER POLE
  - N45°E 1.13' - NAIL & TAG IN POWER POLE
  - S02°E 7.20' - NAIL & TAG IN POWER POLE
  - N40°E 86.50' - NAIL & TAG IN TWIN CHERRY



APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 12/14/95

Signed by [Signature]  
Surveyor's Michigan License No. 9433

Date 12-22-95