

SURVEY & REMONUMENTATION

DEC 16 1996

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 117

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1E	E - 5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-REMONUMENTATION

2 DEC 96 3:27 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-------------------------------|-------------------------------------|
| 1848 JOHN MULLETT SET POST | WIT.-SAME AS (3),(4)&(5) |
| WIT.-(1)Y. PINE 12 N44E 34 | 1973 PAUL LAPHAM SURVEY |
| (2)W. PINE 12 N48E 39 | WIT.-SAME AS (3),(4)&(5) |
| 1950 DUNDAS-WORKING DRAWING | 1973 PAUL LAPHAM SURVEY |
| WIT.-NONE | WIT.-SAME AS (3),(4)&(5) |
| 1971 PAUL LAPHAM L.C.R.C.#24 | 1976+/- PAUL LAPHAM-WORKING DRAWING |
| FOUND 1" IRON BAR | SECTION SUBDIVISION |
| WIT.-(3)S80W 72.50 12" OAK | 1976 PAUL LAPHAM SURVEY |
| (4)N45W 77.95 14" OAK | WIT.-SAME AS (3),(4)&(5) |
| (5)NORTH 116.80 MAPLE CLUSTER | 1979 PAUL LAPHAM-WORKING DRAWING |
| 1971 PAUL LAPHAM SURVEY | SECTION SUBDIVISION |

- 1982 P LAPHAM SURVEY WIT.-SAME AS (3),(4)&(5)
- 1985 P LAPHAM SURVEY WIT.-SAME AS (3),(4)&(5)
- 1985 P LAPHAM SURVEY WIT.-SAME AS (3),(4)&(5)

APPROVED LAND CORNER
 P.A. 745 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 11/2/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 24" BAR IN GRADED AREA (OLD ROADBED) IN LINE WITH COUNTY ROAD TO EAST EXTENDED. FOUND (4)--SPIKE IN 18" OAK, N50W+/-; MEAS. 78.10, REC. 77.95. FOUND (3)--OLD BLAZE IN FACE OF 16" OAK, S80W; MEAS. 71.8+/-, REC. 72.50. FOUND C.I. EAST 133.65, REC. BY PAUL LAPHAM IN SURVEY #3367. SET GLADWIN RE-MON.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: SW CORNER OF SECTION 9
 SET 5/8" X 3/8" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

- WITNESSES:
 N50W 18" OAK, SPIKE, 78.10'
 S80W 16" OAK, N&T, 72.35'
 EAST C.I. 133.50'
 N40E 8" MAPLE, N&T, 175.75'
 S60W CLUSTER 8" OAKS, SPIKE, 25.75'



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-29-96