

SURVEY & REMONUMENTATION

DEC 16 1996

GLADWIN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 118

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1E	F - 3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:27 P.M.

RONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1846 JOHN MULLETT
NO CORNER SET
- 1975 CAVANAGH SURVEY
WIT.-NONE
- 1946 PLAT WINTER'S HAVEN
LIBER 2 PAGE 30
- 1990 PAUL LAPHAM-REPLAT
ELK LAKE SUBD.
- 1947 GOGGINS-PLAT
ARNHOLDS INDIAN ELK SUBD.
- 1950+/- DUNDAS-WORKING DRAWING
WIT.-NONE

APPROVED LAND CORNER
P.A. 305 of 1990
Gladwin County

Co. Rep. John M. [Signature]
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" X 30" PIPE WITH 1 1/4" X 30" REBAR IN PIPE, WITH FLAGGING, IN C/L OF ROADS NORTH & EAST, LINE OF POST WEST TO LAKE, RECORDED IN PLAT OF ARNHOLDS INDIAN ELK SUBD. & WINTER'S HAVEN.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: 1/4 CORNER COMMON TO SECTIONS 4 & 9
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:
N80W 14" OAK, SPIKE, 35.34'
N40W 14" OAK, SPIKE, 51.90'
N75E TRIPLE OAK, 2@12"-1@8", SPIKE, 37.25'
S60E NE COR. HOUSE 85.65'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96