

**SURVEY & REMONUMENTATION**

**OCT 23 1998**

GLADWIN County Remonumentation

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **205**

For corners in:

GLADWIN  
(County)

Located in:

Corner Code #

- |                                    |                   |       |
|------------------------------------|-------------------|-------|
| 1. Public Land Survey              | T20N R01E         | M-5   |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:42:56 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:  
**M-5:** 1846 Louis Mason (5)N35W W. Pine 83.40

Set Sec Post-Cor 12 & 13, T20N, R1E  
Wit-(1)Cedar 5 S10W 6 links  
(2)Do 5 N65W 12 links

1994 Lapham  
Wit-same as (3),(4)&(5)

1967 Geo Henning-Fd 1/2" Bar in Sec Cor  
Wit-none

1995-96 D.N.R.--LCRC#372 Fd T-Iron  
Wit-(6)10" J. Pine S50E 57.24  
(7)12" Spruce S58W 43.81  
(8)Fence Post N44W 51.77  
(9)4" Pine N43E 57.80

1985 Lapham--Fd 1/2" Iron  
Wit-(3)S45W 6" Pine 44.00  
(4)S45E P.P. 60.48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**M-5:** Found T-iron over 1/2" iron in centerline of North-South road and centerline of road to East. Corner agrees with 1967 survey by Henning. It agrees with witnesses (3), (5), (7) & (9). Accepted found T-iron, removed and set Gladwin County Remonumentation. See dossier for additional information.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**M-5:** Corner common to Sections 12 & 13, on township line. Set 5/8" x 36" rerod with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:  
S45W 10" Spruce, nail & tag, 43.80'  
N35W 14" W. Pine, nail & tag 83.63  
N43E 5" Pine, spike, 57.85'  
N65E 8" W. Pine, nail & tag, 96.60'

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 8/11/98

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-5-98