

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **206**

SECTION

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R01E	M-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:43:16 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on May _____, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:
- M-6: 1837 Louis Mason-Set 1/4 Post Sec Post
 - Wit-(1)B. Ash 11 S49W 11 links
 - (2)Cedar 6 N75W 28 links
 - 1967 Hennings Fd 1/2" Iron
 - Wit-none
 - 1977 Hennings Fd 1/2" Iron
 - Wit-none
 - 1978 Lapham (survey & dwg)-Fd 1/2" Pipe
 - Wit-(3)S60W T.P. 39.70
 - (4)West Dead End Sign
 - (5)N60W 10" Poplar 38.00
 - (6)S80E 4" Poplar 43.80
 - 1985 Lapham (survey & dwg)-Fd 1/2" Bar
 - Wit-(7)N30E 8" Cedar 59.0
 - (8)N80E C.I. 33.00
 - (9)S45W Tele Riser 39.90
 - 1994 Lapham (survey & dwg)
 - Wit-same as (7),(8) & (9)
 - 1996 DNR-LCRC#372 Fd 1/2" Rerod
 - Wit-(10)4" W. Pine N52E 48.81
 - (11)18" W. Pine N88E 56.34
 - (12)6" W. Pine S34E 73.67

(13)5" W. Birch S66W 49.98

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-6: Found 1/2" rerod inside 3/4" x 20" pipe in centerline of North-South road. Corner agrees with 1967 survey by Henning. Corner fits witnesses (6), (7) & (11). Accepted 1/2" iron. Removed and Set Gladwin County Remonumentation.

See dossier for detailed report.


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- M-6: E 1/4 Corner of Section 13, located on township line. Set 5/8" x 36" rerod with Gladwin County Remonumentation Cap marked P.S.#27458.

- Witnesses:
- N30E 10" Cedar, (survey cap & spike) 58.98'
 - S80E 8" Poplar, spike, 43.75'
 - N88E 18" W. Pine, spike, 56.35'
 - S45E 8" Poplar, nail & tag, 73.20'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6/14/98

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-5-98