

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 210

For corners in

GLADWIN (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R01E	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:44:07 PM

PONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

2. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on April _____, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- M-10: 1837 Louis Mason Set 1/4 Post
 - Wit-(1) Cedar 6 S48W 25 Lks
 - (2) W. Pine 9 N61W 8 Lks
- 1977 Lapham (working dwg & LCRC#158) Set C.I.
 - Wit-(3) N45W 47.65 8" Maple
 - (4) S75E 48.35 8" W. Pine
 - (5) N70E 36.0 4" Maple
- 1996 DNR (LCRC#376) Set Capped Iron Set Cor midway & on-line
 - Wit-(6) 4-8" Maple Clp N58E 54.11
 - (7) 6" Maple S41E 57.58
 - (8) 12" W. Pine S27W 70.43
 - (9) 8" W. Pine N15W 65.76
 - (10) 1/2" Rerod N24E 25.08

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-10: Found 5/8" rerod with DNR cap, 6 ft. West of centerline of county road. Accepted corner as part of retracement of Henning 1967 survey. Found witnesses (6),(7) & (9). Agree with location of corner. (1977 Lapham corner, LCRC#158, was not accepted) See dossier & LCRC#376 for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10: East 1/4 of Section 25, on township line. Set Gladwin County Remonumentation cap marked P.S.#27458 on found DNR 5/8"X34" rerod.

- Witnesses:
- S41E 6" Maple, spike, 57.58'
 - N58E Male Stump, Spike, 54.11'
 - N15W 8" W. Pine, spike, 65.76'
 - N80E 12" W. Pine, nail & tag, 54.30'
 - West Cedar Post, 25.5'
 - N25E 12" rerod, 25.08'



APPROVED LAND CORNER
P.A. 215 of 1990
Gladwin County

Co. Rep. J. L. Meyers
Date 8/11/98

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-5-98