

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **213**

SECTION

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	A-6
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:44:45 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Mark R Robison, in a field survey on May, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- A-6: 1837 Louis Mason-Set 1/4 Post Sec Post
 - 1985 Lapham (survey & dwg)-Fd 1/2" Bar
 - Wit-(1)B. Ash 11 S49W 11 links
 - Wit-(7)N30E 8" Cedar 59.0
 - (2)Cedar 6 N75W 28 links
 - (8)N80E C.I. 33.00
 - 1967 Hennings Fd 1/2" Iron; Wit-none
 - (9)S45W Tele Riser 39.90
 - 1977 Hennings Fd 1/2" Iron; Wit-none
 - 1994 Lapham (survey & dwg)
 - 1978 Lapham (survey & dwg)-Fd 1/2" Pipe
 - Wit-same as (7),(8) & (9)
 - Wit-(3)S60W T.P. 39.70
 - 1996 DNR-LCRC#372 Fd 1/2" Rerod
 - (4)West Dead End Sign
 - Wit-(10)4" W. Pine N52E 48.81
 - (5)N60W 10" Poplar 38.00
 - (11)18" W. Pine N88E 56.34
 - (6)S80E 4" Poplar 43.80
 - (12)6" W. Pine S34E 73.67
 - (13)5" W. Birch S66W 49.98

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- A-6: Found 1/2" rerod inside 3/4" x 20" pipe in centerline of North-South road. Corner agrees with 1967 survey by Henning. Corner fits witnesses (6), (7) & (11). Accepted 1/2" iron. Removed and Set Gladwin County Remonumentation. See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-6: W 1/4 Corner of Section 18, located on township line. Set 5/8" x 36" rerod with Gladwin County Remonumentation Cap marked P.S.#27458.

Witnesses:
N30E 10" Cedar, (survey cap & spike) 58.98'
S80E 8" Poplar, spike, 43.75'
N88E 18" W. Pine, spike, 56.35'
S45E 8" Poplar, nail & tag, 73.20'

APPROVED LAND CORNER
P.A. 315 of 1990
Gladwin County

Co. Rep. [Signature]
Date 5/11/98



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-5-98