

**SURVEY & REMONUMENTATION**

**OCT 23 1998**

GLADWIN County Remonumentation

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **217**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T20N R02E</u>	<u>A-10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:45:30 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on April, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

**A-10:** 1837 Louis Mason Set 1/4 Post  
Wit-(1) Cedar 6 S48W 25 Lks  
(2) W. Pine 9 N61W 8 Lks  
  
1977 Lapham (working dwg & LCRC#158)  
Set C.I.  
Wit-(3) N45W 47.65 8" Maple  
(4) S75E 48.35 8" W. Pine  
(5) N70E 36.0 4" Maple

1996 DNR (LCRC#376) Set Capped Iron  
Set Cor midway & on-line  
Wit-(6) 4-8" Maple Clip N58E 54.11  
(7) 6" Maple S41E 57.58  
(8) 12" W. Pine S27W 70.43  
(9) 8" W. Pine N15W 65.76  
(10) 1/2" Rerod N24E 25.08

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**A-10:** Found 5/8" rerod with DNR cap, 6 ft. West of centerline of county road. Accepted corner as part of retracement of Henning 1967 survey. Found witnesses (6),(7) & (9). Agree with location of corner. (1977 Lapham corner, LCRC#158, was not accepted) See dossier & LCRC#376 for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**A-10:** W 1/4 Corner, Section 30, on township line. Set Gladwin County Remonumentation cap marked P.S.#27458 on found DNR 5/8" x 34" rerod.  
Witnesses:  
S41E 6" Maple, spike, 57.58'  
N58E Maple stump, spike, 54.11'  
N15W 8" W. Pine, spike, 65.76'  
N80E 12" W. Pine, nail & tag, 54.30'  
West Cedar Post 25.5'  
N24E 1/2" rerod 25.08'

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 8/11/98

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-5-98