

OCT 23 1998

SECTION

GLADWIN County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 220

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	B-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:46:09 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on June _____, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

B-7: 1846 John Mullett Set 1/4 Sec Post
Wit-(1)Beech 10 N65E 14
(2)Hemlock 8 S60W 12

1908 CSR
Set Cedar Stake & Wagon Skew 3 1/2" x 10"
Wit-(3)Pine St 24 N40E 87 Lks

1967 Henning (dwg) Set Iron - No Wit

1995-96 DNR (working dwg & LCRC#374)
Fd 1/2" Iron Pipe
Wit-(8)12" Ash N47E 36.45
(9)12" Poplar S16E 9.74
(10)6" Ash S49W 16.28
(11)5" Ash N20W 15.48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7: Found 1/2" Galvanized pipe with Cedar Post. Agrees with witnesses (8), (9), (10) & (11), replaced 1/2" Pipe with Gladwin County Remonumentation Monument. Corner agrees with 1967 Henning survey.

See dossier for additional details.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7: Corner common to Sections 18 & 19. Set 5/8" x 36" rod with Gladwin County Remonumentation Cap marked P.S.#27458.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Witnesses:
N47E 12" Ash, spike, 36.45'
S16E 12" Poplar, spike, 9.74'
S49W 6" Ash, spike, 16.28'
N20W 5" Ash, spike, 15.48'

Co. Rep. [Signature]
Date 6/11/98

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-5-98