

**SURVEY & REMONUMENTATION**

**OCT 23 1998**

**SECTION**

**GLADWIN County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 001 PAGE 221**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T20N R02E</u>	<u>B-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:46:20 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on June     , 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

**B-9:** 1846 John Mullett Set 1/4 Sec Post  
Wit-(1)Hemlock 12 N49W 20  
(2)Do 16 S31E 11

Wit-(6)4" Ash N77E 22.79  
(7)6" Ash S9E 16.72  
(8)4" Ash S68W 23.12  
(9)5" Ash N45W 34.84  
(10)1/2" Rerod N04E 26.08

1977 Lapham (working dwg & LCRC#158)  
Set C.I.  
Wit-(3)N45W 9.58 12" Poplar  
(4)N45E 8.53 12" Poplar  
(5)S45E 10.40 12" Poplar

1995-96 DNR (LCRC#375) Set DNR Mon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**B-9:** Found DNR Monument with Cedar Post at North side of small beaver flooding. Agrees with witnesses (6), (7), (8) & (9).  
(Corner by Lapham LCRC#158 was not accepted)

See dossier and LCRC#375 for additional details.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**B-9:** Corner common to Sections 19 & 30. Accepted DNR Monument as recorded on LCRC#375, Gladwin County Public Records.

Witnesses:  
N77E 4" Ash, spike, 22.79'  
S09E 6" Ash, spike, 16.72'  
S68W 4" Ash, spike, 23.12'  
N45W 5" Ash, spike, 34.84'  
N04E 1/2" rerod 26.08'

**APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County**

Co. Rep. [Signature]  
Date 8/11/98

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-5-98