

SURVEY & REMONUMENTATION

OCT 23 1998

SECTION

GLADWIN County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 222

For corners in

GLADWIN (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	B-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-CORNER

13 OCT 1998 12:46:33 PM

RONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Mark R Robison, in a field survey on May _____, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
	6	5		4		3		2		1		
	7	8	9	10	11	12						
	18	17	16	15	14	13						
	19	20	21	22	23	24						
	30	29	28	27	26	25						
	31	32	33	34	35	36						

- A. Description of original monument and accessories and/or subsequent restoration:
- B-11: 1846 John Mullett Set 1/4 Sec Post
 Wit-(1)B. Ash 6 N70W 7
 (2)Cedar 8 S69E 15
 1974 Radcliffe LCRC#103
 Found 1/2" x 1 1/2" Flat Iron
 Wit-(3)10" Poplar N25E 47.12
 (4)P.P. North 28.88
 (5)9" Pine S35W 36.98
 - 1977 McGinnis LCRC#162
 Found 1/2" x 1 1/2" Iron
 Wit-(6)N5W 28.5 face P.P.
 (7)South 32.75 face Conc. Mon.
 (8)S10W 40.00 2" Tamarack
 - 1996 DNR LCRC#377 Found Pinched Pipe
 Wit-(9)P.P. N06E 32.03
 (10)4" Sq. Mon S4W 32.91
 (11)4" W. Pine S33E 45.69
 (12)P.P. N79E 105.90
 - 1976 Higgins survey Wit-none
 1976 Lapham working dwg

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B-11: Found 1 1/2" x 1/4" x 12" Flat Iron in centerline of county road opposite property line to North (brush line) at slight angle. See dossier for additional information.
 Excavated and did not find any evidence of other corners.
 Set Gladwin County Remonumentation from found iron and witnesses (7), (8) & (11).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-11: Corner common to Sections 30 & 31. Set 5/8" x 36" rerod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

- Witnesses:
- South Conc. Mon. (face) 32.75'
 - N05W Power Pole, nail & tag, 32.21'
 - N79E Power Pole, nail & tag, 105.74'
 - S33E 5" W. Pine, spike, 45.63'
 - N45E 5" W. Pine, nail & tag, 79.83'
 - P.K. Nail 2 ft. North & East

APPROVED LAND CORNER
 P.A. 315 of 1990
 Gladwin County

Co. Rep. John M. Meyer
 Date 6/11/98

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 10-5-98