

**SURVEY & REMONUMENTATION**

OCT 23 1998

GLADWIN County Remonumentation

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 225

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	C-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:47:09 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May \_\_\_\_\_, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

**C-7:** 1846 John Mullett  
Set Post Sec's 17, 18, 19 & 20  
Wit-(1)Hemlock 8 N13W 33  
(2)Do 18 S21E 15  
1967 Henning Found 3/8" Bar  
Wit-(3)P.P. N24W 61.0  
(4)B.M. Monument S56W 33.75  
1972 Edmands Eng LCRC#51 Wit-same (3)&(4)  
Wit-(5)W 24.5 to Corner Post  
1995-96 DNR (work dwg & LCRC#374)  
Found cement nail  
Replaced with 5/8" x 16" rerod with cap  
Wit-(6)6" Birch S66W 64.16  
(7)10" U. Pole N26W 63.12  
(8)8" Aspen S53E 47.26  
(9)14" Aspen N85E 48.52

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**C-7:** Found 5/8" x 16" Capped Iron (DNR) in centerline of North-South road, 25 ft. South of drive to West. Agrees with witnesses (6), (7) & (9). Fits 1967 survey by Henning. Excavated and did not find any other corners. Set Gladwin County Remonumentation in position of DNR corner. See dossier for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**C-7:** Corner common to Sections 17, 18, 19 & 20. Set 5/8" x 36" rerod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:  
S66W 6" W. Birch, spike, 64.15'  
N30W Power Pole, nail & tag, 63.03'  
N85E 16" Poplar, spike, 48.52  
N85W 14" Ash, nail & tag, 77.65'  
P.K. Nail 2 ft. North & South

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Gladwin County

Co. Rep. John Mullett  
Date 8/16/98

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-5-98