

**SURVEY & REMONUMENTATION**

**OCT 23 1998**

GLADWIN County Remonumentation

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **226**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	C-8
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-CORNER

13 OCT 1998 12:47:21 PM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on May \_\_\_\_\_, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:  
**C-8:** 1846 John Mullett Set 1/4 Post cut nail  
 Wit-(1)W. Pine 12 N39W 17 Replaced with 5/8" x 16" rerod  
 (2)Maple 14 S57E 11 Wit-(5)14" W. Pine N33W 82.84  
 (6)14" R. Pine S60W 65.23  
 1967 Henning Found 3/8" Bar (7)4" W. Pine S67E 55.59  
 Wit-(3)6" Pine S30W 80.04 (8)11" W. Pine N51E 55.08  
 (4)8" Pine N75W 51.27  
 1966-72 Edmands Eng LCRC#51 1997 Lapham survey w/ 1995 DNR witnesses  
 Wit-same (3) & (4) Wit-same as (5) & (6)  
 (9)S35E 50.70 12" W. Pine  
 1995 DNR work dwg & LCRC#375 Fd (10)S80E 55.60 6" W. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**C-8:** Found 5/8" x 16" Capped Iron (DNR) 2 ft. East of centerline of place of found 5/8" Iron.  
 road. Corner agrees with witnesses as recorded on LCRC#375, Gladwin County Records. Also agrees with 1967 survey by Henning. Found witness (4), recorded: 8" Pine N75W 51.27. Measured to center of 12" - 14" Pine Stump N75W 51 ft. +/- Set Gladwin County Remonumentation in See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**C-8:** Corner common to Sections 19 & 20. Set 5/8" x 36" rerod in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

Witnesses:  
 N33W 14" W. Pine, nail & tag, 82.84'  
 S60W 14" R. Pine, spike, 62.23'  
 N51E 12" W. Pine, spike, 55.08'  
 S35E 4" W. Pine, nail & tag, 50.70'  
 S67E 6" W. Pine, spike, 55.60'

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Gladwin County

Co. Rep. [Signature]  
 Date 8/11/98

Signed by [Signature]  
 Surveyor's Michigan License No. 27458



Date 10-5-98