

SURVEY & REMONUMENTATION

OCT 23 1998

SECTION

GLADWIN County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **228**

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R02E	C-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:47:45 PM

RONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on May _____, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:
C-10: 1846 John Mullett Set 1/4 Post Wit-(5)N45E 40.43 4" Maple
 Wit-(1)Hemlock 8 N71E 9 (6)S35E 53.27 Tele Pole
 (2)Do 6 S70W 13 (7)West 62.5 6" Basswood
 1981 Lapham survey
 1966 Edmands Eng. road plans Wit.-same as (5), (6), (7)
 Wit-(3)Cottonwood NW 78.00 1982 Higgins survey Wit-none
 (4)P.Pole S/SW 103.60
 1968 Lapham survey Wit-none
 1976 Lapham (work dwg, survey, LCRC#158) Wit-(8)10" Cottonwood NW 78.00
 Fd 1" Pipe; Set 1/2" C.I. (9)P. Pole S/SW 103.6
 1996 DNR LCRC#377 Found C.I. Wit-(10)12" Basswood N37E 72.85

- (11)Power Pole S26W 103.97
(12)10" Ash N50W 65.42
(13)St Sign Post S46E 45.85

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-10: Found 1/2" x 16" rerod over 1" pipe in centerline of North-South road and road to East. Agrees with witnesses (4) & (9). Corner fits DNR LCRC#377. 1" iron fits 1966 Edmands Eng. road plans. Accepted found 1" iron as in place.

See dossier for additional information.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-10: Corner common to Sections 29 & 30. Set 1/2" rerod in found 1" pipe in Monument Box with Gladwin County Remonumentation cap marked P.S.#27458.

- Witnesses:
 N26W Power Pole, spike, 103.92'
 N37E 12" Basswood, spike, 72.80'
 S43E 7" Maple, nail & tag, 65.00'
 N50W 10" Ash, spike, 65.42'
 P.K. Nail 2 ft. North & East

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8/11/98

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-5-98