

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin Located In _____ Corner Code # _____
(County)

| | | | | | |
|--------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey | T | <u>20N</u> | R | <u>2E</u> | <u>D9</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 20, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|---|----|---|---|----|---|----|---|----|---|----|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | ● | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

D9 – GLO – J. Mullett – 1846 – Set ¼ post
 W. Pine 20" S46°W 21 L.
 Hemlock 8" N51°E 30 L.
 - J. E. Richardson-1968 – fd. point of post and one original witness was found with the lower markings still visible.
 Set 5/8" x 3' bar; S. Maple 6" S50°E 29.80';
 S. Maple 14" N56°W 66.10'; S. Maple 6" S12°W 32.11';
 W. Pine 20" S46°W 13.86' - original
 - LCRC #500 – M. R. Robison – 2000

Set capped iron
 North 18.53' set N & T in 4" W. Pine
 East 13.20' set N & T in 8" W. Pine
 S10°E 10.25' to set N & T in 12" Birch
 N60°W 10.05' to set N & T in 6" Birch

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D9 – ¼ Corner common to Sec. 20 & 29 – Found 5/8" rebar in agreement with apparent remains of GLO 20" ± WPS per Richardson. Fits Richardson's witnesses. Based on physical evidence and Richardson's notes the 5/8" rebar is accepted as a careful and faithful perpetuation of the position of the original corner.

- Reference Pt. – Found ½" capped iron rebar #27595 per LCRC #500 is N8° 57'W 42.66' from 'D9'. This capped iron rebar fits Richardson's survey map numbers but it is apparent from the physical evidence that there is a blunder in Richardson's survey dimensions. ½" CIR #27595 not utilized as 'D9' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D9 – Add stamped 2" Alum. Cap to fd. 5/8" rebar
 S84°E 20.33' to set N & T in N. side 18" W. Pine scribed 'XBT'
 S8°W 32.19' to set N & T in E. side 17" R. Maple scribed 'XBT' (JER)
 N59°W 66.31' to set N & T in NE side 36" S. Maple scribed 'XBT' (JER)
 S51°E 30.42' to set N & T in NE side leaning 16' R. Maple scribed 'XBT' (JER)
 N8° 57'W 42.66' to ½" CIR #27595 – Ref. Pt. -
 N10° 41'W 24.44' to Fd. ½" CIR #27595
 Set Blue Carsonite Post 1' N.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007