

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2E</u>	<u>D11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on Dec. 15, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			●										
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D11 - GLO - J. Mullett - 1846 - Set 1/4 Post
 Hemlock 10" S72°W 25 L.
 Hemlock 10" N54°E 23 L.
 - Rec. Survey - L. 1, p. 810 - R. L. Higgins - 1978
 and notes from Lapham and Assoc.
 Set 1/2" x 18" steel bar - SP
 10" Poplar N30°W 12.0'
 2" Poplar N45°E 10.45'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D11 - 1/4 corner common to Sections 29 & 32, T20N, R2E - Found 1/2" x 18" rebar with broken cap per R. L. Higgins. Higgins BT's gone. No GLO evidence found. Fd. 1/2" iron is 2.98' W. of split distance between 'C11' and 'E11'. Fd. 1/2" x 18" rebar is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D11 - Replaced 1/2" x 18" CIR w/ stamped 4" DNR Aluminum cap on 1" x 3' long galv. iron pipe.
 N74°W 48.78' to set N & T in N. side 3" R. Maple in clp. of 7 scribed 'XBT'
 S42°W 29.82' to set N & T in NW side 3" Oak
 S01°W 80.36' to set N & T in E. side 2" W. Pine
 S69°E 58.18' to set N & T in N. side 2" Oak
 Set Blue Carsonite Post 1' North



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007