

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2E</u>	<u>E9</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Craig W. McVean, in a field survey on March 7, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E9 - GLO - J. Mullett - 1846 - Set post
 Hemlock 14" S41°E 10 L.
 Hemlock 10" N61°W 41 L.
 - CCC Notes - 1930's - North 160:00 - Set Random post. W. 319.61 - N & S random line 1.41 South of Random post. W. 320 - Set random post
 - J. E. Richardson Notes - 1968
 Searched for but didn't find corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E9 - Section corner common to sections 20, 21, 28 & 29, T20N, R2E - No evidence of GLO corner or witnesses. Set DNR monument by double proportion to GLO from found corners at 'D9', 'E8', 'E11' and 'M9'. Centerline N-S 2-track is 78' East. Measures South to check GLO Stream Call of 1386' S. - "S. Bank Stream - SW - 6 L." and find N. edge of beaver pond is 1360' S. and S. Edge of beaver pond is 1429' South. DNR Mon. is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E9 - Stamped 4" DNR aluminum cap on 1" x 3' long galv. iron pipe.
 S24°W 6.46' to set N & T in SE side 7" Oak scribed 'XBT'
 N33°E 53.27' to set N & T in SE side 9" Spruce scribed 'XBT'
 N7°W 90.23' to set N & T in W. side 7" Oak scribed 'XBT'
 S61°E 4.95' to set N & T in SW side 10" W. Birch
 N53°E 19.39' to set N & T in NW side 6" Oak
 Set Blue Carsonite Post 1' East



Signed by: Craig W. McVean Date: 5/9/2007
 Surveyor's Michigan License No.: 39088