

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_  
 Gladwin \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	20N	R	2E	E10
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Mar. 1, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29	●	28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E10 – GLO – Set ¼ Post – J. Mullet 1846  
 Y. Pine 14" S20°W 23 L.  
 Hemlock 18" N19°E 19 L.  
 - CCC Notes – 1930's – North between Sec. 28 & 29 – 120.00 - Set Random ¼ Post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E10 – ¼ Corner common to Sections 28 & 29 - Searched large area around calculated SP position but found no conclusive GLO evidence. Set 4" DNR Aluminum cap on 1" x 36" galvanized iron pipe by single proportion to GLO between Fd. 'E11' and reestablished 'E9'. DNR monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E10 – 4" Aluminum DNR cap on 1" x 36" galv. iron pipe.  
 Set Blue Carsonite post 1' North  
 S78°E 48.85' to set N & T in S. side 2" Oak  
 S7°W 72.60' to set N & T in E. side 4" Oak  
 N50°W 85.31' to set N & T in NE side 3" Oak  
 N9°E 75.94' to set N & T in W. side 2" Oak



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007