

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2E</u>	<u>E12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32	●	33		34		35		36		
13													

I, Craig W. McVean, in a field survey on Feb. 28, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E12 - GLO - Set 1/4 Post - J. Mullett - 1846
 Spruce 10" N45°E 14 L.
 Tamarack 10" S66°E 29 L.
 - CCC notes - 1930's - North between Sec. 32 & 33 in swamp - 40.00 -
 Set random 1/4 post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E12 - 1/4 Common to Sections 32 & 33 - Searched in swamp but no GLO evidence found. Set 4" Aluminum DNR Cap on 1" x 5' long galvanized iron pipe, single proportion to GLO between fd. 'E13' and 'E11', in leather-leaf and tamarack swamp. DNR Monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12 - 4" Aluminum DNR cap on 1" x 5' long galv. iron pipe.
 Set Blue Carsonite post 1' North
 S24°W 13.50' to set N & T in E. side 5" Tamarack
 N61°W 18.94' to set N & T in NE side 5" Tamarack
 N28°E 30.00' to set N & T in W. side 3" Tamarack
 S63°E 45.00' to set 3/4" x 1.8' long iron pipe



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007