## LAND CORNER RECORDATION CERTIFICATE

		•	iiiig ixequ	illement of Act	74, MICH. F7	A 1970	,						
For Corners In: Gladwin (County)		Located In		Corner Code	#								
<ol> <li>Public Land Survey</li> <li>Property Controlling in Section</li> </ol>	s	T 20N T	R _2E R R	F13	- -								
Miscellaneous     Property in Section	s s	T	RR		- - -		Regist	er of C	)eeds	Stamp	& File	Numi	ber
4. Lot No:	Recorde	d Plat:				А В	c D	_	F G	ш.		<i>.</i> .	
5. Private Claims:						2 -6-	1	E		H I		K L	
I, <u>Craig W. McVean</u> , in a 1 requirements of PA 74, Mid and 2 above were in conforthe current manual of sur Interior, Bureau of Land Ma corner points mentioned in of the Michigan Board of established, re-established,	chigan PA o rmance with vey instruct unagement o lines 3, 4 au f Land Sur	of 1970, the regulations in regulations of the or by a decread 5 above weyors or b	corner point and rules the united State of a Court were in confoy a Decree	ts mentioned in line herefore as require tes Department of t of Law and/or that ormance with the rule of a Court of L	nder es 1 d in the the ules aw;	3 4 - 7 - 5 6 - 18 - 7 8 - 19 - 9		,	9			12	3
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.					1	30-30-	32		33	-27    -34	35—	36	5— 5—
A. Description of original monument and accessories and/or subsequent restoration:													
F13 – GLO – Set ¼ Pos Hemlock 7" N12°E		on – 1837											

- Hemlock 12" N56°W 37 L.
  - CCC Notes 1930's West on N. Bdy of Sec. 4, T19N, R2E, 280.00 - Set Random 1/4 Post.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F13 Standard ¼ Corner common to Sec. 33, T20N, R2E Fd. 5/8" x 18" rebar w/ cap #4672 in line with Gravel Rd. North and 4'± N. of centerline of Gravel Rd. West. No GLO evidence. 5/8" CIR is 3' West of split distance between 'E13' and 'G13'. Accepted 5/8" CIR as the best available evidence of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F13 Replaced Cap #4672 on 5/8" x 18" rebar w/ stamped 2 ½" Brass Cap on 5/8" x 34" rebar w/ 4" x 8" long PVC w/ conc. around cap. Add some crockery around.

Set Blue Carsonite Post w/ loc. tag 33' E West 29.04' to 'F1' – T19N, R2E – 2 1/2" Brass Cap

N40°E 69.28' to set N & T in NW side 4" Spruce scribed 'SCBT'

S84°E 61.90' to set N & T in N. side 7" Tamarack scribed 'SCBT'

S50°E 114.30' to set N & T in NE side 15" R. Maple scribed 'SCBT'

Surveyor's Michigan License No.: 39088

Date:

OF MICHIGA CRAIG W. **McVEAN** ROFESSIONA SURVEYOR No. 39088 POFESSION